

# Boston Spa School

## Project Information

*Address:* Clifford Moor Road  
Boston Spa  
Wetherby  
West Yorkshire  
LS23

*Facility:* 101.40m x 63.00m Synthetic Turf Pitch

*Sports:* Football, Hockey, Tennis, Netball, Aerobic Activities

*Pitch System:*

- New VHAF NottsSward 1300 needlepunched sand filled  
Grass - LAID ON EXISTING
- VHAF Rubber Crumb Shockpad
- Dynamic granular stone base
- Underlying piped drainage system

*Construction Cost:* £145,000

*Completed:* Originally Built: 1996  
Resurfaced: August 2011

*Specialist Contractor:* Cleveland Land Services

### *Points of Interest:*

- The original construction was installed in 1996. The project in 2011 was to replace the existing sand filled surface with a replacement high quality multi-purpose synthetic grass.
- The existing VHAF Rubber Crumb Shockpad & dynamic base construction has proven to last the life of 2 carpets at sites throughout the UK providing customers with a system that can be reused rather than replaced and reduce the costs of refurbishment in comparison to other performance layers and shock-pads.



To find out more, call 01455 883730,  
email [info@nottssport.com](mailto:info@nottssport.com) or visit  
[www.nottssport.com](http://www.nottssport.com)

**nottssport** Synthetic Surfacing

